

SCHEDULE 3: PERIMETER FENCE AND GATE

ITEM NO.	DESCRIPTION	UNIT	QUANT	RATE	AMOUNT
3.1	FENCING				
	SECTION 1 :DEALING WITH EXISTING FENCING				
1.1	Remove existing 1800mm high diamond mesh fence, together with all poles and strain wires and deliver it to Oshakati town council as directed by the Client	m	325		
	SECTION 2 : PALISADE FENCING				
2.1	Supply and Install new 1800mm high x3000,mm palisade panels as per details provided on the drawing or to match the existing one complete made of 50x50x3,0mm equal angle iron vertical members at 150mm centre to centre, supported by 50x50x3mm equal angle top and bottom horizontal bracing placed at 2 metres interaval and welded on poles (elsewhere mesured).	m	325		
2.2	Supply and Install 2.4m high 100X100X2mm Square Hallow Section (SHS) poles at 3m interaval to support parisade fencing as described in the drawing	Qty	110		
2.3	Supply and fabricate the 6000mm Steel sliding gate formed of 75mmx50mm rectangle tubings include all the 80mm gate wheels and gate guide , sliding angle rails wel the 60mmx60mmx6mm angle iron and 10mm round bar on top to run smoothly	no	2		
2.4	Casting of 100x2mm SHS poles into 300X300X600mm deep 25MPa Concrete as per detail in the attached drawing.	m3	7.2		
2.5	Painting of palisade Fencing and Poles with approved colour by the council Steel Paint enamel to match existing palisade Fencing at the open market	Sum	1		
	SECTION 3 : CLEANING AND FINISHING				
3.1	Cleaning and finishing of site after completion of the works and the removal of all construction rubble and debris to approved spoil sites	Sum	1		
3.2					
3.3					
TOTAL					

#REF!

PROJECT NUMBER: OM/04/2024

SUMMARY OF SCHEDULE OF QUANTITIES

SCHEDULE	DESCRIPTION	AMOUNT
1	PRELIMINARY AND GENERAL	#REF!
2	FENCING EARTHWORKS	#REF!
3	PERIMETER FENCING	\$ -
		\$ -
	SUB TOTAL A	#REF!
	CONTINGENCIES (5% OF SUBTOTAL A) The sum provided here is under the sole control of the Porject Manager and to be used at discretion of the Porject Manager and could be deducted in whole or in part if not required.	#REF!
	SUB TOTAL B	#REF!
	VALUE-ADDED TAX (15% ON SUBTOTAL B)	#REF!
	TOTAL CONTRACT AMOUNT	#REF!

**BILL OF QUANTITIES
FOR
FENCING AT OSHAKATI-OMATALA WOOD AND KAPANA ZONE**

TOTAL TENDER AMOUNT

#REF!



**906 Sam Nujoma Road, Civic
Center, Oshakati, Namibia +264
65 229 500 fax number +264 65
220 435. postal address
Private Bag 5530, Oshakati, Namibia**